

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-147-19013-00-0 #

API NUMBER N/A

LEASE NAME Furse

WELL NUMBER B-1

       Ft. from S Section Line

       Ft. from E Section Line

SEC. 3 TWP. 1S RGE. 18E (E) or (W)

COUNTY Phillips

Date Well Completed       

Plugging Commenced 6-14-89

Plugging Completed 6-14-89

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Hawn Petroleum, Inc.

ADDRESS P.O. Box 1065

PHONE# (316) 241-0115 OPERATORS LICENSE NO. 5646

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on June 9, 1989 (date)

by Dale Balthazor (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached?       

Producing Formation Kansas City Depth to Top        Bottom 3492 T.D. 3492

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from        feet to        feet each set. Ran 2" tubing to 3348' & mixed 25 sacks cement. Shot Anhydrite @ 1660'-shot off tubing at 1460' and pulled tubing. Ran cement down 4 1/2" casing at 1000 # max. pressure, mixed 65 sacks, then mixed 4 sacks hulls with 160 sacks cement & shut in at 400#. Down annulus (8 5/8 casing) at @ 500# max. pressure mixed 1 sack hulls with 150 sacks cement & shut in @ 200#. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company, Inc. License No.       

Address P.O. Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hawn Petroleum, Inc.

STATE OF Kansas COUNTY OF McPherson, ss.


Bob Robertson (Employee of Operator) of        above-described well, being first duly sworn on oath, says: That I have knowledge of the facts of the statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bob Robertson

(Address) P.O. Box 1065, McPherson, KS 67460

SUBSCRIBED AND SWORN TO before me this 29th day of June, 19 89

Julie Ann Blew  
Notary Public



RECEIVED  
STATE CORPORATION COMMISSION  
JUN 30 1989  
CONSERVATION DIVISION  
Wichita, Kansas