


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15-147-00683-00-00
WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Phillips County. Sec. 20 Twp. 1 Rge. (E) 17 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE SE
Lease Owner The Bay Petroleum Corporation
Lease Name Frazer Well No. 1
Office Address Box 513, Chase, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 9, 19 51
Application for plugging filed. (written) June 21, 19 51
Application for plugging approved. June 19, 19 51
Plugging commenced June 9, 19 51
Plugging completed June 9, 19 51
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3730 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	233'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pumped mud in hole to 225' through drill pipe,
Set plug at 225' w/15 sacks cement,
Mud to 35',
Plug at 35' w/10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 23 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Bay Petroleum Corporation
Address Box 513, Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
Glen E. Armour (employee of owner) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) Glen E. Armour

SUBSCRIBED AND SWORN to before me this 21 day of June, 19 51

My commission expires May 20, 1954
Lincoln Gray Notary Public.

PLUGGING
FILE SEC 20 T 1 R 7 W
BOX 513 CHASE 88

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 508 E. -Murdock, Wichita, Kansas

Chose


Company - BAY PETROLEUM & WESTGATE-GREENLAND
 Farm - Frazer No. 1

SEC. 20 T. 1 R. 17W
 SE SE SE

15-147-00683-00-00

Total Depth. 3730
 Conn. 5-30-51 Comp. 6-9-51
 Shot or Treated.
 Contractor. Jackson Drlg.
 Issued. 6-30-51

County. Phillips
 KANSAS



CASING:
 8 5/8" 233' cem. w/140 sx.

Elevation. 2186

Production. Dry

Figures Indicate Bottom of Formations.

soil, clay & gravel	90
sand	160
shale	980
shale & shells	1250
shale & sand	1450
shale & shells	2010
shale & lime	3475
lime	3612
lime cherty	3628
lime	3667
lime & shale	3730
Total Depth	

Tops:
 Heebner 3440
 Lansing 3489

D.S.T. 3238-58. Open 45 mins. Rec. 45' slightly
 oil cut mud- 240' slightly oily wtr & mud.
 D.S.T. 3582-3610. Open 1 hr. rec. 50'
 slightly oil cut mud.
 D. S. T. 3616-30. Open 30 mins. rec.
 335' mud.

All Meas. From top of Derrick Floor.

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 13 1951
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 20 T 1 R 17W
 BOOK PAGE 88 LINE 22