


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

15-183-00003-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Smith County, Sec. 21 Twp. 1 Rge. 15W(E) (W)
Location as "NE/CNW/SW" or footage from lines SW SW NE
Lease Owner Bennett & Roberts Drilling Co.
Lease Name Bates Well No. 1
Office Address Russell, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7/27 1954
Application for plugging filed 7/27 verbally 1954
Application for plugging approved 7/27 verbally 1954
Plugging commenced 7/27 1954
Plugging completed 7/27 1954
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren H. Horner
Producing formation Depth to top Bottom Total Depth of Well 4205 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	205'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole to 200' w/heavy mud. Pushed bottom plug to 200'. 1/3 sack hulls & 20 sacks cement. Filled hole to 35'. Pushed plug to 35'. 1/3 sack hulls and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor
Address

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Harold Wurst (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst
Russell, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of August, 19 54
Notary Public.

My commission expires 6/17/58

24-7368-S 3-53-20M

PLUGGING
FILE SEC 21 T 1 R 15W
BOOK PAGE 51 LINE 39

RECEIVED
STATE CORPORATION COMMISSION
AUG 4 1954
CONSERVATION DIVISION
Wichita, Kansas

15-183-00003-00-00

Bennett & Roberts Drilling Co.
Bates #1

SW SW NE Sec. 21-1-11W
Smith County, Kansas

R.T.D. 4205

Comm: 7/14/54
Comp: 7/27/54

Set 8 5/8" @ 205' w/140 sx cmt.

Tops:	
Cimmerron Anhyd.	1800
Topeka Lime	3010-898
Heebner Shale	3238-1126
Toronto Lime	3264-1152
Lansing K.C.	3280-1168
Base K.C.	3530-1418
Marmaton	3545-1433
Cherokee	3696-1584
Mississippi Chert	3860-1748
Hunton(Devnoian?)	3878-1766
Viola	3904-1792
Simpson Shale	4104-1992
Simpson Sand	4129-2017
Simpson Dolomite	4138-2026
Arbuckle	4150-2038

Formation:	Depth:
Shale & Clay	110
Yellow Clay	180
Blue Shale & Shells	205
Blue Shale	540
White Shale	595
Shale black	870
Sand, Shale, Shells	1320
Shale & Sand	1520
Shale & Shells	1630
Red Rock & Shale	1800
Anhydrite	1825
Shale & Shells	1860
Shale & Lime	2450
Lime	2590
Lime & Shale	3193
Lime	3597
Lime & Shale	3860
Chert	3867
Lime & Chert	3905
Lime, Shale Chert	3942
Lime & Chert	4009
Cherty Lime	4058
Lime	4235
Shale	4141
Sand & Dolomite	4145
Shale	4150
Arbuckle(Chert in top)	4205

STATE OF KANSAS)
RUSSELL COUNTY) SS.

I hereby certify that the above information is true and correct
to the best of my knowledge.

BENNETT & ROBERTS DRILLING CO.

Harold W. ...

Subscribed and sworn to before me this 3rd day of August, 1954.

Uran ...
Notary Public

My Commission Expires 6/17/58

PLUGGING
FILE SEC 21 T 1 R 15W
BOOK PAGE 51 LINE 39

RECEIVED
STATE CORPORATION COMMISSION
AUG 4 1954
CONSERVATION DIVISION
Wichita, Kansas