

15-147-20357-00-00

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Phillips SEC. 29 TWP. 1S RGE. 17W E/W  
 Location as in quarters or footage from lines:  
C NE NE

			x

Lease Owner KRM Petroleum Corporation  
 Lease Name Imm Well No. 1-29  
 Office Address 820 Guaranty Bank Bldg. 817 17th St., Denver, CO 80202  
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
 Date Well Completed December 23, 1981  
 Application for plugging filed Verbally, December 23, 1981  
 Plugging commenced 7:00 P.M. December 23, 1981  
 Plugging completed 9:45 p.m. December 23, 1981  
 Reason for abandonment of well or producing formation Dry Hole

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt

Producing formation N/A Depth to top N/A bottom N/A T.D. N/A

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	24# 244'	None

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Plugged with 135 sacks 50/50 Pozmix (4% gel, 3% CaCl)

Set 1st plug @ 1200' w/70 sacks

Set 2nd plug @ 200' w/40 sacks

Set 3rd plug @ 40' w/10 sacks

10 sacks Rathole

5 sacks Mousehole

RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN - 8 1982  
 CONSERVATION DIVISION  
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oilwell Cementing, Inc.

P.O. Box 169, Great Bend, KS 67530

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

C.K. Morrison

(~~owner~~ ~~operator~~) or (employee of owner)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) C.K. Morrison

555 N. Woodlawn, Bldg. 1 - Suite 207  
 Wichita, (Address) KS 67208

SUBSCRIBED AND SWORN TO before me this 7th day of January, 19 82

Suzanne P. Graef  
 Suzanne P. Graef Notary Public.

My Commission expires: October 26, 1985



January 6, 1982

CONTRACTOR'S WELL LOG 15-147-20357-00-00

OPERATOR: KRM Petroleum Corporation  
 CONTRACTOR: KANDRILCO, Ltd.  
 WELL NAME: Imm #1-29  
 LOCATION: C NE NE Section 29, T1S-R17W  
 Phillips County, Kansas  
 API NO.: 15-147-20,357  
 COMMENCED: December 14, 1981  
 COMPLETED: December 23, 1981

Drilled 245' of 12 1/4" hole. Set 224' of new 8 5/8" 24# casing at 224' (KB) with 165 sacks common - 3% CaCl, 2% gel. Cement did circulate to surface. Plug was down at 8:00 a.m., December 15, 1981.

<u>FORMATION</u>	<u>TOP'</u>	<u>BOTTOM'</u>
Sand & Shells	0	245
Shells & Shale	245	1350
Shale & Sand	1350	2000
Lime & Shale	2000	2580
Shale & Lime	2580	3277
Lime & Shale	3277	3730
Lime & Chert	3730	3950
Chert & Lime	3950	4050

RTD 4050'. Plugged to abandon. Cemented with 135 sacks 50-50 pozmix, 4% gel, 3% CaCl. Set 70 sacks at 1200', 40 sacks at 200', 10 sacks at 40', 10 sacks Rathole and 5 sacks Mousehole. Plugging was completed at 9:45 p.m. December 23, 1981.

STATE OF KANSAS, COUNTY OF SEDGWICK, SS:


I, C. K. Morrison, President, KANDRILCO, Ltd., do hereby certify that the above is a true and correct copy of the Driller's Log for the KRM Petroleum Corporation Imm #1-29 well located in Phillips County, Kansas.

KANDRILCO, Ltd.

RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN - 8 1982  
 CONSERVATION DIVISION  
 Wichita, Kansas

*C.K. Morrison*  
 C.K. Morrison - President

Subscribed and sworn to before me, a Notary Public, in and for the County and State aforesaid, as of this 6th day of January, 1982.



*Suzanne P. Graef*  
 Suzanne P. Graef  
 Notary Public

My Commission Expires: October 26, 1983