


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

15-147-00086-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Phillips County, Sec. 7 Twp. 1S Rge. 17W (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE NE SE
Lease Owner Imperial Petroleum Company, Inc.
Lease Name Schermerhorn Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 9, 1951
Application for plugging filed May 9, 1951
Application for plugging approved May 9, 1951
Plugging commenced 1:00 a.m. May 9, 1951
Plugging completed 3:00 a.m. May 9, 1951
Reason for abandonment of well or producing formation Commercial quantity of oil not found
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Stough
Producing formation Depth to top Bottom Total Depth of Well 3600 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	190	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3600 to 180' filled with heavy rotary mud
180 to 120' wooden plug, $\frac{1}{2}$ sack hulls & 15 sacks cement
120 to 40' filled with mud
40' to 00' wooden plug, $\frac{1}{2}$ sack hulls & 10 sacks cement

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Imperial Petroleum Company, Inc.
Address Union National Bank Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK
CLINTON ENGSTRAND, agent for (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Clinton Engstrand*
1006 Central Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 11th day of May, 1951

My commission expires 6-5-54

23-5091-s 8-50-10M

RECEIVED
STATE CORPORATION COMMISSION
MAY 14 1951
CONSERVATION DIVISION
Wichita, Kansas
Notary Public.

PLUGGING
FILE SEC 7-1-17W
BOOK PAGE 80 LINE 38

IMPERIAL PETROLEUM CO., INC.
SCHERMERHORN # 1

15-142-00086-00-00

SE NE SE Sec. 7-18-17W
Phillips County, Kansas

Total Depth: 3600'
Comm: 4-28-51
Comp: 5-9-51

<u>Casing</u>	<u>Cement</u>
8 5/8" Set @ 190'	125 Sacks
5 1/2" - None	

<u>FORMATION</u>	<u>DEPTH</u>
Surface clay & sand	0 - 70
Shale	70 - 120
Shale shells	120 - 845
Shale & shells	845 - 1075
Sand	1075 - 1105
Shale & shells	1105 - 1690
Shale & lime shells	1690 - 1920
Shale & lime	1920 - 2300
Shale shells	2300 - 2405
Lime (Hard)	2405 - 2420
Shale & lime streaks	2420 - 2475
Shale & lime	2475 - 3025
Lime	3025 - 3090
Lime & shale breaks	3090 - 3150
Lime & shale	3150 - 3200
Lime	3200 - 3280
Lime & shale	3280 - 3335
Lime	3335 - 3600

STATE OF KANSAS)
) SS
 SEDGWICK COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

[Signature]

Subscribed and sworn to before me this 11th day of May, 1951.

RECEIVED
 CONSERVATION COMMISSION
 MAY 12 1951
 CONSERVATION DIVISION
 WICHITA, KANSAS

[Signature]
 Notary Public

My commission expires: 6-5-54

PLUGGING
 FILE SEC 7T-1R-70
 BOOK PAGE 80 LINE 58