


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

15-147-00074-00-00  
WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Phillips County. Sec. 23 Twp. 1 Rge. ~~17~~ 17 (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE SW SE  
Lease Owner The Bay Petroleum Corporation  
Lease Name Schluntz Well No. 1  
Office Address Box 957, Denver Colorado  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 28 19 51  
Application for plugging filed April 17 19 51  
Application for plugging approved April 18 19 51  
Plugging commenced May 27 19 51  
Plugging completed June 5 19 51  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19...  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Depth to top Bottom Total Depth of Well 3650 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	214'	none
				5 1/2"	3647'	1204.45'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Lane Wells bridging plug installed at 3472 - hole filled with sand from 3472 to 3440; Four sacks of cement placed with bailer to form cement plug from 3440 to 3408; Hole mudded from 3408 to 214; installed rock bridge from 214 to 204; Fifteen sacks of cement poured in hole to form cement bridge from 204 to 159; Hole mudded from 159 to 35 ft; Rock installed from 35 ft to 30 ft; ten sacks of cement poured in hole to form cement plug to surface. Plugging complete.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Bay Petroleum Corporation  
Address Box 513, Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.  
Glen E. Armour (employee of owner)

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) *Glen E. Armour*  
Box 513 Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 14 day of June, 19 51

My commission expires May 20, 1954

23-5091-S 8-50-10M

**PLUGGING**  
FILE SEC 23 T 1 R 17 W  
BOOK PAGE 79 LINE 17

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 15 1951  
CONSERVATION DIVISION  
Wichita, Kansas

15-147-00074-00-00

COMPANY

Westgate Greenland Oil Co.

CONTRACTOR

Jackson Drilling Corporation

FARM

Schluntz # 1

LOCATION

NE SW SE Section 23-1-17W

ELEVATION

Phillips County, Kansas  
2118

COMMENCED

March 2, 1951

COMPLETED

March 14, 1951 - Rotary

-----

0 - 8	Cellar
8 - 50	Shale and sand
50 - 214	shale and shells
214 - 376	Shale
376 - 616	shells and shale
616 - 677	sandy shale
677 - 981	Shale and shells
981 - 1495	Shale w/sand streaks
1495 - 1620	Shale
1620 - 1890	Redbed and shale
1890 - 2295	Lime and shale
2295 - 2325	Lime
2325 - 3387	Lime and shale
3387 - 3650	Lime
3650	Total depth

-----

8 5/8" 24# casing set at 214 feet. Cemented with 140 sacks cement and 2 sacks calcium chloride

5 1/2" casing set at 3647'. Cemented with 150 sacks cement.

Drill stem test 3459-3491. Open 45 minutes - recovered 25 feet mud

Drill stem test 3495-3530. Open 1 1/4 hrs, recovered 30 feet mud

Drill stem test 3553-3607. Open 1 1/4 hrs, recovered 130 feet watery mud

Tops- Heebner 3352  
Lansing 3403

Potential

All measurements from top of derrick floor

STATE OF KANSAS  
APR 18 1951  
CONSERVATION DIVISION  
Wichita, Kansas

C E R T I F I C A T E

I, Clare A. Stewart, do hereby certify that the above and foregoing is a true and correct copy of log of Schluntz # 1, Section 23-1-17W, Phillips County, Kansas, as reflected by the files of the Jackson Drilling Corporation

S/ Clare A. Stewart  
Clare A Stewart

Subscribed and sworn to before me, a Notary Public, within and for Johnson County, Kansas, this 23rd day of March, 1951

S/ Dorothy J. Wilson  
Dorothy J. Wilson

My commission expires November 30, 1951

PLUGGINS  
FILE SEC 23-1-17W  
BOOK PAGE 74 LINE 17