

#6

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-147-20,436 ~~66-00~~

COUNTY Phillips

LEASE NAME Babcock WELL# 1

SPOT LOCATION SW SW SW

SEC. 18 TWP. 1 RGE. 17 (E) or (W)

PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.
TYPE OR PRINT

LEASE OPERATOR Ladd Petroleum Corporation

PHONE # () 316-792-3571

OPERATORS LICENSE NO. 6029

CHARACTER OF WELL D&A (OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DATE WELL COMPLETED 1-23-84 PLUGGING COMMENCED 1-23-84

PLUGGING COMPLETED 1-23-84 REASON FOR ABANDONMENT OF WELL OR PRODUCING
FORMATION Dry Hole

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Hays - Marion Schmidt - Gilbert Bartholomew

Is ACO-1 FILED? Yes IF NOT, IS WELL LOG ATTACHED?

PRODUCING FORMATION DEPTH TO TOP BOTTOM T.D. 4005'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS | CASING RECORD


FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	239'	8-5/8"	232'	None

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. 200 sks 50/50 Poz. 6% Gel, 3% CC, 2 sks Flo Seal
20 sks @ 3900'
20 sks @ 1840' By Halliburton
100 sks @ 1250' Completed 1-23-84,
40 sks @ 240' 8:30 p.m.
10 sks in rat hole

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Allen Drilling Company LICENSE No. 5418
ADDRESS Box 1389, Great Bend, Kansas 67530

STATE OF KANSAS COUNTY OF BARTON, SS



Dale L. Smith (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT. SO HELP ME GOD.

(SIGNATURE) Dale L. Smith

(ADDRESS) Box 1389, Great Bend, KS 67530


BEFORE ME THIS 25th DAY OF January, 1984

Wanda Nichols

NOT RECEIVED
STATE CORPORATION COMMISSION

MAR 16 1984 FORM CP-4
REVISED 06-83

CONSERVATION DIVISION
Wichita, Kansas



RECEIVED
STATE CORPORATION COMMISSION
APR 02 1984
SUBSCRIBED AND SWORN TO
CONSERVATION DIVISION
Wichita, Kansas

MY COMMISSION EXPIRES: 12-10-87