

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-147-20187-00-00

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

API NUMBER \_\_\_\_\_  
LEASE NAME PAUL IMM  
WELL NUMBER #1  
SPOT LOCATION C E/2 SW  
SEC. 3 TWP. 1S RGE. 18W (E) or  
COUNTY PHILLIPS  
Date Well Completed \_\_\_\_\_  
Plugging Commenced 4-25-84  
Plugging Completed 6-8-84

LEASE OPERATOR BAIRD OIL COMPANY, INC.  
ADDRESS P.O. BOX 428 LOGAN, KANSAS 67646

PHONE # ( ) 689-7456 OPERATORS LICENSE NO. 5352

Character of Well OIL  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? HAYS, KANSAS

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3476'

Show depth and thickness of all water, oil and gas formations.

**OIL, GAS OR WATER RECORDS**

**CASING RECORD**

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	214'	none
				4-1/2"	3475'	1423'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged off bottom with 4 sacks cement, sand to 3275' and 4 sacks cement. Shot casing @2014', 1818', 1619', 1423' and pulled a total of 36 joints (1423') of 4-1/2" casing. Plugged surface with 2 hulls, 5 gel, 140 cement, 15 gel, released plug and displaced with 50 cement. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050  
Address P.O. Box 347 Chase, Kansas 67524

RECEIVED  
STATE CORPORATION COMMISSION

JUN 13 1984

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

CONSERVATION DIVISION  
Wichita, Kansas

(Signature) R. Darrell Kelso  
(Address) P.O. Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 12 day of June, 1984

IRENE HOOVER  
State of Kansas  
My Comm. Exp. Aug. 15 1985

Irene Hoover  
NOTARY PUBLIC

My Commission expires.