

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-147-00401-00-00

API NUMBER ~~15-147-00000-00-00~~

LEASE NAME ~~Fischer~~ B Fisher

WELL NUMBER 1

4620 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 4 TWP. 1 RGE. 18W (E) (W)

COUNTY Phillips

Date Well Completed 8-4-61

Plugging Commenced 6-2-00

Plugging Completed 6-2-00

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Bruce Oil Company, L.L.C.

ADDRESS 1704 Limestone Rd., McPherson, KS 67460

PHONE# (316) 241-2938 OPERATORS LICENSE NO. 5610

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on May 31, 2000 (date)

by Carl Goodrow (KCC District Agent's Name)

Is ACO-1 filed? no If not, is well log attached? yes

Producing Formation Lan-Kansas City Depth to Top 3193 Bottom 3415 T.D. 3420

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
surface	clay and shale	0	140	8 5/8	140	none
surfaceto TD	shale and lime	140	3420	4 1/2	3418	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Perforated Anhydrite and Dakota with 2 shots each at 1060 feet and 1900 feet. Mixed 230 sax 60/40 pozmix cement 10% gel and 400#hulls, pumped down casing. Mixed 50 sax 60/40 pozmix cement 10% gel, pumped down 8 5/8. Shut in. Plugging complete.

(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION

Name of Plugging Contractor none License No. JUN 6 2000

Address

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lonny Bruce/Bruce Oil Company CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas COUNTY OF McPherson, ss.

Lonny Bruce (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Lonny Bruce
(Address) McPherson, Kansas

SUBSCRIBED AND SWORN TO before me this 5th day of June, 2000

BEVERLY A. FOLCK
Notary Public - State of Kansas
My Appt. Expires 12-13-01

Beverly A. Folck
Notary Public

My Commission Expires: 12-13-01