


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-147-00059-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Phillips County, Sec. 21 Twp. 1 Rge. 17 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SW SW SW
Lease Owner O'Neill Tank Co., Inc.
Lease Name Rolland #1 Well No.
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 3-31-59 19
Plugging completed 4-3-59 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3760' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	198'	none
				5-1/2"	3759'	1481'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked the hole to 3760' and found it open.
Ran 5 sacks of cement at 3760' with dump bailer.
Pulled casing to 550' and circulated pipe with
26 sacks of gel mud and pumped in 20 sacks of
cement at 550'. ~~RUN~~ Pulled pipe to 180' and pumped
in 20 more sacks of cement. Pulled rest of casing,
cleared hole and bailed mud to 35', set rock bridge
to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETED

RECEIVED
STATE CORPORATION COMMISSION
MAY 4 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
I, Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Noel Knight*
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 14th day of April, 1959

Thomas V. Doyne
Notary Public.

My commission expires 9-27-62

PLUGGING
FILE SEC 21 T 1 R 12W
BOOK PAGE 15 LINE 31

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY BAY PETROLEUM CORP. & WESTGATE GREENLAND OIL SEC. 21 T. 1 R. 17W
FARM Rolland NO. 1 LOC. SW SW SW

Chase


15-147-00059-00-00

TOTAL DEPTH 3760
COMM. 2-5-51

COMP. 3-16-51

COUNTY Phillips

KANSAS



SHOT OR TREATED
CONTRACTOR Jackson Drlg. Corporation
ISSUED 4-7-51

CASING

8 5/8" 198' cem. w/140 sx
5 1/2" 3759' cem. w/150 sx

ELEVATION 2201

PRODUCTION Pot. 83 bbls. oil
+ 9% water

FIGURES INDICATE BOTTOM OF FORMATIONS

soil & clay	20
shale	165
sand	190
shale	1080
sand & shale	1515
sand	1565
shale w/sand	1605
shale & redbed	1950
shale & shells	2110
shale & lime	2275
shale	2415
lime	2450
shale & lime	2490
sandy lime w/chert	2550
lime & shale	2850
lime	2875
lime & shale	3511
lime	3760

Total depth

All measurements from top of Derrick floor.

Tops:

Topeka	3238
Heebner	3453
Dodge	3485
Lansing	3502
Base Kansas City	3736

Remarks:

Drill stem test 3593-3626. Open 30 minutes - recovered 310 feet of free oil with gas. Bottom hole pressure 1050. Perf. 24/3597-3605. Bail. 1 BOPH; Perf. 48/3605-18, 46 GOFH. 500 acid. 3 hr. swabbing gauge. 11.2 BO 1st hr. 8.04 2nd hr. 11.02 3rd hr. no water

RECEIVED
STATE CORPORATION COMMISSION
FEB 14 1959
CONSERVATION DIVISION
WICHITA, KANSAS

PLUGGING
FILE SEC. 21 T. 1 R. 17W
BOOK PAGE 15 LINE 31