

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 18 1963  
CONSERVATION DIVISION  
Wichita, Kansas

15-147-19016-00-00

Operator's Full Name W. P. Simmons Oil Co

Complete Address: Box 54 Alma, Neb

Lease Name Walker Well No. 1

Location CE<sup>1</sup>/<sub>2</sub> SE SW Sec. 4 Twp. 1 Rge. (E) (W) 18

County Phillips Total Depth 3460

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: B & D Casing Pulling

Address: Ellinwood, Kansas License No. 236

Operation Completed: Hour 8PM Day 13 Month 2 Year 63

The Above well was plugged as follows:

8 5/8" 154' circulated with cement - 4 1/2" 3460' with 75 sax cement,  
Perf 3350'  
Filled with sand to 3320', set 3 sax cement with dump bailer, pulled  
2000' 4 1/2" to 500', circulated hole with heavy mud through 4 1/2" at  
500' ( 30 sax Gel), displaced 20 sax cement through 4 1/2" at 500',  
heavy mud to 165', displaced 20 sax cement through 4 1/2" at 165',  
heavy mud to 40', set bridge and filled with cement to bottom  
cellar.

Mudding and cementing by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: Edon Kelly  
Well Plugging Supervisor

INVOICED  
DATE 2/18/63  
INV. NO. 6600-u