

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 28 1962

CONSERVATION DIVISION
Wichita, Kansas

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

19020
15-147-~~30133~~-000

File No. _____ County: Phillips

Location: CE $\frac{1}{2}$ SE SE Sec. 4 Twp. 1 Rge. _____ (E) _____ (W) 18

Name of Field: _____ Total Depth: 3425

I have this date completed supervision of plugging of:

Lease Name: Walker Well No. A-1

Operator's Full Name: W. P. Simmons Oil Co

Complete Address: Box 355 Alma, Neb

Plugging Contractor Southwest Casing Pulling

Address: Great Bend, Kans License No. 399

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 2PM Day 21 Month 5 Year 62

The above well was plugged as follows:

8 5/8" 162' circulated with cement - 4 $\frac{1}{2}$ " 3425' with 150 sax cement - Perf 3221' - sand back to 3200', set 4 sax cement with dump bailer.

Pulled 2740' 4 $\frac{1}{2}$ " to 500', circulated hole with heavy mud through 4 $\frac{1}{2}$ " at 500' (31 sax Gel), displaced 20 sax cement through 4 $\frac{1}{2}$ " at 500', heavy mud to 160', displaced 20 sax cement through 4 $\frac{1}{2}$ " - heavy mud to 35', set bridge and filled to bottom cellar with cement.

Mudding and cementing by Globe Cementing Co.

Signed: Edon Petty
Conservation Division Agent

Reviewed: Harold Hallis
Field Supervisor

Remarks: