

DISTRICT CONSERVATION AGENT'S REPORT

SR

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

15-147-00648-00-00

FILE NO. 74-15

LOCATION SE SE SW

SEC. 6 TWP. 1 RGE. 18

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Farley

Operator Honaker Drg Co Address Great Bend, Kans

Field _____ County Phillips

Total Depth 3410' Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 223' circulated with cement - 5 1/2" at 3409'

with 175 sax cement behind. Lane Wells plugs to 3328', top
perf at 3284'.

Filled with chat to 3275', set 4 sax cement with dump

bailer, pulled 2422' 5 1/2", filled hole with mud to 220',

set rock bridge and 15 sax cement, filled with mud to 35'

set rock and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAY 7 - 1951

CONSERVATION DIVISION
Wichita, Kansas

Edna Kelly
District Conservation Agent

Date 5-1-51

PLUGGING
FILE SEC 6 T 1 R 18
BOOK PAGE 74 LINE 15