

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

15-147-00167-00-00

FILE NO. _____

LOCATION NW NE MW

SEC. 7 TWP. 1 RGE. 18

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Gebhard

Operator Honaker Drg Co, INC. Address Great Bend, Kans

Field _____ County Phillips

Total Depth 3449 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 165' with cement to surface - 5 1/2" at 3448'
with 175 sax cement behind. Drilled out to 3423, top
perf 3408'.

Filled with chat to 3400', set 4 sax cement with dump
bailer, pulled 1525' 5 1/2", filled hole with mud to 160',
set rock and 15 sax cement, filled with mud to 55', set
rock bridge and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUN 16 1951

CONSERVATION DIVISION
Wichita, Kansas

[Signature]
District Conservation Agent

Date 6-14-51

PLUGGING
FILE SEC 7 T 1 R 18 W
BOOK PAGE 85 LINE 28