

DISTRICT CONSERVATION AGENT'S REPORT

R
15-147-00077-00-00

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW SW NW

SEC. 9 TWP. 1 RGE. 18 W

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Seyler

Operator Alpine Oil & Royalty Address Wichita, Kans

Field _____ County Phillips

Total Depth 3489' Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 200' circulated with cement - 5 1/2" at 3489' with
12s sax cement behind, Baker plug at 3380', top perf at 3361',
Filled with chat to 3350' set 4 sax cement with dump bailer,
pulled 2820' 5 1/2", filled hole with heavy mud to 190', set rock
bridge and 15 sax cement, filled with heavy mud to 35', set
rock bridge and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
FEB 16 1951
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 9 T 1 R 18 W
BOOK PAGE 68 LINE 16

Edwin Lett
District Conservation Agent
Date 2-14-51