

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 2 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Leland R. Baird 15-147-00143-00-01
Complete Address Logan, Kansas 67646
Lease Name Knappe Well No. 1
Location NW NW SE Sec. 8 Twp. 1 Rge. (E) (W) 18
County Phillips Total Depth 3583'
Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor SW Casing Pulling Co.
Address Box 364 Great Bend, Kansas 67530 License No. 399
Operation Completed: Hour 1:30 P Day 29 Month 10 Year 1973

The above well was plugged as follows:

Total Depth 3583' 10 3/4 csg set at 203' cwc
5 1/2 csg set at 3539' cw 270 sk cem.
PBTD 3505' with perf. 3310-12-14 & 3470-71-73.
Set 5 1/2 wood plug at 3275' - poured 25' sand - dumped 5 sk cem W/dump bailer.
Cutoff and recovered 2400' of 5 1/2 csg.
Pumped down 10 5/8 csg with 15 sk gel & water W/500 lbs hulls -- 70 sk cem. -- 15 sk gel & water -- released 10 3/4 plug and pumped 80 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo F. Massey
Well Plugging Supervisor

INVOICED

DATE 11/2/73
INV. NO. 8107-W