

*10*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAR 26 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

15-147-19019-00-00

Operator's Full Name C. R. Moffitt  
Complete Address: 809 Bitting Bldg Wichita, Kans.  
Lease Name Pretzler Well No. 1  
Location NE NE SE Sec. 5 Twp. 1 Rge.      (E)      (W) 18  
County Phillips Total Depth 3443  
Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated:       
Plugging Contractor: Glenn & Smith  
Address: Ellinwood, Kansas License No. 396  
Operation Completed: Hour 1PM Day 23 Month 3 Year 63

The Above well was plugged as follows:

8 5/8" 200' circulated with cement - 5 1/2" 3442' with 100 sax cement - Perf 3419' - filled with sand to 3400', set 4 sax cement with dump bailer.  
pulled 2800' 5 1/2" to 550', circulated hole with heavy mud at 550', through 5 1/2" ( 18 sax Gel), displaced 20 sax cement through 5 1/2" at 550', heavy mud to 200', displaced 20 sax cement through 5 1/2" at 200', heavy mud to 35', set bridge and filled to bottom cellar with cement.

Mudding and cementing by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edward Letey*  
Well Plugging Supervisor

DATE 3/26/63

INV. NO. 6775-W