

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 15 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-147-19015-00-00

Operator's Full Name C. R. Moffitt & Assoc.

Complete Address: 809 Bitting Bldg Wichita, Kansas

Lease Name Walker Well No. 2

Location SW NW SW Sec. 4 Twp. 1 Rge. (E) (W) 18

County Phillips Total Depth 3495

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Glenn & Smith

Address: Ellinwood, Kans License No. 396

Operation Completed: Hour 8:30PM Day 9 Month 3 Year 63

The Above well was plugged as follows:

8 5/8" 200' circulated with cement - 5 1/2" 3495' with 100 sax cement -
Perf. 3429' - filled with sand to 3420', set 4 sax cement with dump bailer.
Pulled 2800' 5 1/2" to 550', circulated hole with heavy mud at 550' through
5 1/2" (20 sax gel), displaced 20 sax cement through 5 1/2" at 550', heavy
mud to 200', displaced 20 sax cement through 5 1/2" at 200', heavy mud to 35',
cement 35' to bottom cellar.

Mudding and cementing by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

DATE 3/15/63
INV. NO. 6723-W

Signed: Edon Petty
Well Plugging Supervisor

INVOICED