

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

15-147-30180-00-00

FILE NO. 77-24

LOCATION SE SE SE

SEC. 7 TWP. 1 RGE. 18

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Byenstrom **B. JURSTROM**

Operator Black Cat Oil Co Address Great Bend, Kans

Field _____ County Phillips

Total Depth 3728 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 160' circulated with cement - 5 1/2" at 3442'
with 100 sax cement behind - Lane Wells plugs to 3343',
top perf 3336'.

Filled with sand to 3320', set 4 sax cement with dump bailer,
pulled 2850' 5 1/2", mudded hole to 165', set rock and 15 sax
cement, filled with mud to 35', set rock and 10 sax cement
to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAY 15 1951

CONSERVATION DIVISION

Wichita, Kansas

J. Edson
District Conservation Agent

Date 5-9-51

PLUGGING
FILE SEC 7 TWP 1 R 18
BOOK PAGE 27 LINE 24