

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 25 1965

CONSERVATION DIVISION
Wichita, Kansas

15-147-19017-00-00

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Bovaird Supply Co
Complete Address: Box 897 Great Bend, Kans
Lease Name Kauk Well No. 1
Location NE NE NW Sec. 4 Twp. 1 Rge. (E) (W) 18
County Phillips Total Depth 3458
Abandoned Oil Well x Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Hull Casing Pulling Co
Address: Sterling, Colo License No. 576
Operation Completed: Hour 3:30PM Day 21 Month 1 Year 65

The Above well was plugged as follows:

8 5/8" 220' - 5 1/2" 3457 with 100 sax cement - PB 3370' Perf 3332'
Filled with sand to 3320', set 4 sax cement with dump bailer - pulled
2730' 5 1/2" to 600', circulated hole with heavy gel mud through 5 1/2" at
600' (30 sax Gel), displaced 20 sax cement through 5 1/2" at 600', heavy
mud to 240', displaced 20 sax cement through 5 1/2" at 240', heavy mud
to 35', set bridge and cement to bottom cellar.

Mudding and cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Eldon Petty
Well Plugging Supervisor

DATE 1/26/65
INV. NO. 576-W