

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22336-00-00
Spot: NESESE Sec/Twnshp/Rge: 33-16S-12W
890 feet from S Section Line, 330 feet from E Section Line
Lease Name: PROSSER Well #: 1
County: BARTON Total Vertical Depth: 3317 feet

Operator License No.: 6357
Op Name: WEBCO OIL CO., INC.
Address: 2136 NE 90 AVE.
HOISINGTON, KS 67544

CIBP Size: feet: 3268
PROD Size: 4.5 feet: 3314 175 SX CMT
SURF Size: 8.625 feet: 315 210 SX CMT

\$107⁸⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/13/2004 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: BRIAN SCHUMACHER Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: Ordered 185 sxs 60/40 pozmix - 10% gel - 500# hulls.
Dakota 0' - 114'. Anhy. 745' - 768'. Salt 1200' - 1400'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/13/2004 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

DS&W Well Service, Inc. sanded bottom off to 2960' with 4 sxs cement with dump bailer.
Shot off casing at 1600' - pulled to 1425' and pumped 70 sxs 60/40 pozmix with 300# hulls mixed in.
Pulled casing to 775' - pumped 40 sxs 60/40 pozmix with 100# hulls mixed in.
Pulled casing to 300' - pumped 60 sxs 60/40 pozmix with 100# hulls - cement circulated to surface.
POOH. Pulled rest of casing.
Hole was standing full of cement.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3101 | 3125 | | |
| 3062 | 3088 | | |

RECEIVED
FEB 19 2004
KCC WICHITA

Remarks: COPELAND ACID & CEMENTING COMPANY-TICKET #24122.

Plugged through: CSG

District: 04

Signed [Signature]
(TECHNICIAN)

INVOICED

DATE 2-19-04

INV. NO. 2004061202

Form CP-2/3

FEB 16 2004

WMAOICFP

REIF OIL OPERATIONS
 614 N. ELM #1 PROSSER 33-16-12W
 HOISINGTON, KS 67544 100'S. SNE SE SE
 CONTR FUTURE DRG. INC. CTY BARTON

GEOL _____ FIELD ODIN
 E NA CM 5/5/81 CARD ISSUED 9/24/81 IP OIL WELL
 FORM & INTV NA

API 15-009-22,336

| TOPS | DEPTH | DATUM |
|------------------|-------|-------|
| NO TOPS RELEASED | | |
| E. RTD | 3400 | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

E 8-5/8" 3100, PROD CSG SET
 NO DST'S REPORTED
 MICT - CO, TSTD (FORM & INTV NA),
 POP, TIGHT HOLE - NO OTHER INFO TO
 BE RELEASED AT PRESENT - WILL RELEASE
 INFO WHEN AVAILABLE

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS