

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-21411-00-00  
Spot: NWSW Sec/Twnshp/Rge: 3-32S-33W  
1503 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: GRAHAM Well #: 2-3  
County: SEWARD Total Vertical Depth: 5843 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: PO BOX 18496 6200 N WESTERN AVE.  
OKLAHOMA CITY, OK 73154

MSSC Size: feet: 3100 WITH 200 SX CMT  
PROD Size: 4.5 feet: 5706 WITH 150 SX CMT  
SURF Size: 8.625 feet: 1771 WITH 750 SX CMT *\$1899<sup>90</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/14/2004 9:45 AM

Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 25 SX CMT & 300# HULLS. LOAD HOLE. PRESSURE TO 500#. PERFORATE AT 1780'. CIRCULATE CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: SCOTT ALBERG  
Date/Time Plugging Completed: 01/19/2004 11:00 AM

WitnessType: COMPLETE (100%)  
KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PUMP 25 SX CMT & 300# HULLS DOWN 4 1/2" CASING. PRESSURE CASING TO 600 PSI. PERFORATE CASING AT 1780'. PUMPED DOWN 4 1/2" WITH 420 SX CMT. DID NOT CIRCULATE TO PIT. BACKSIDE ON VACUUM. 01/19/04: CHECKED CMT INSIDE 4 1/2" & ANNULUS WITH WIRELINE. TOC @ 23' FROM SURFACE. CUT OFF AND CAPPED.


Perfs:

Top	Bot	Thru	Comments
5726	5730		
5551	5556		

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

*Steve Middleton*  
(TECHNICIAN) *on Funeral leave.*

RECEIVED  
FEB 04 2004  
KCC WICHITA

INVOICE  
DATE 2-4-04  
INV. NO. 2004061141