

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24257-00-00
Spot: E2W2NW Sec/Twnshp/Rge: 14-17S-21W
1260 feet from N Section Line, 1020 feet from W Section Line
Lease Name: CONNER Well #: 1-14
County: NESS Total Vertical Depth: 4243 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 372
HAYS, KS 67601

SURF Size: 8.625 feet: 211

#137⁹⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/30/2004 10:15 PM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Revd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: 1ST PLUG AT 1520' WITH 50 SX CMT. 2ND PLUG AT 780' WITH 80 SX CMT. 3RD PLUG AT 230' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: NONE
Date/Time Plugging Completed: 01/30/2004 12:45 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:


1ST PLUG AT 1520' WITH 50 SX CMT. 2ND PLUG AT 780' WITH 80 SX CMT. 3RD PLUG AT 230' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY SWIFT SERVICES.

Plugged through: DP

District: 01



Signed

Steve M Middleton

(TECHNICIAN)

RECEIVED
FEB 04 2004
KCC WICHITA

INVOICED

DATE 2-4-04
INV. NO. 2004061143

Form CP-2/3

for Steve Middleton on funeral leave 2/2/04