

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01577-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 35-9S-23W
990 feet from S Section Line, 4950 feet from E Section Line
Lease Name: DIEBOLT Well #: 2
County: GRAHAM Total Vertical Depth: 4126 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

PROD Size: 5.5 feet: 3959 w/200 sxs cmt
SURF Size: 8.625 feet: 212 w/175 sxs cmt

#134.10

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/16/2004 8:30 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: BOB GRANT Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Method: Ordered out 390 sxs 60/40 pozmix - 10% gel - 600# hulls.
Well squeezed at 3030' w/unknown sxs; 2950' w/150 sxs; 1580' w/225 sxs; 1497' w/270 sxs.

Plugging Proposal Received By: ROGER MOSES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/16/2004 2:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing to 3680' - mixed and pumped 115 sxs cement with 300# hulls.
Pulled up to 2180' - circulated cement with 140 sxs cement with 300# hulls.
POOH. Topped with 20 sxs cement.
S.I.P. 1000#.
Hooked up to the annulus and pumped 50 sxs cement.
S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
3886	3936		
3854	3877		
3822	3830		

RECEIVED
FEB 19 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Jay Pfeifer
(TECHNICIAN)

INVOICED

DATE 2-19-04
INV. NO. 2004061194

FEB 17 2004

AMERADA PETROLEUM CO

#2

DIEBOLT

35-9-23W

NW SW SW

Contr. HERNDON DRILLING COMPANY

GRAHAM

County

E 2440

Comm.

Comp. 8-24-51

IP 2023 BOPD

Tops	Depth	Datum
TOP	3459	-1019
HEEB	3680	-1240
BR LM	3702	-1262
LANS	3718	-1278
B/KC	3936	-1496
SAND	4113	-1673
T.D.	4149	-1709

Casing
 8" 212 DST 3701-79, 2 HRS, 1350' MUO
 CUT OIL, 780' OIL:
 5" 3959 DST 3784-3840, 2 HRS, 720'
 MUD CUT OIL, 2550' OIL:
 DST 3852-3940, 75 MIN, 600'
 MUD CUT OIL, 1620' OIL:
 DST 4102-26, 2 HRS, 270'
 MUD:
 PERF 200 S, 3885-3936,
 92 S, 3854-77:
 SWB 115 BO/5 HRS: ACID
 4000: SWB 103 BO/7 HRS

LAW POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

WADICER