

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-21004-00-00  
Spot: S2SE Sec/Twnshp/Rge: 14-34S-27W  
660 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: CLASSEN 14 Well #: 1  
County: MEADE Total Vertical Depth: 6250 feet

Operator License No.: 5278  
Op Name: E.O.G. RESOURCES INC.  
Address: 20 N. BROADWAY #800  
OKLAHOMA CITY, OK 73102

CIBP Size: feet: 5975 WITH 2 SX CMT  
CIBP Size: feet: 6080  
PROD Size: 2.875 feet: 6250 WITH 300 SX CMT  
SURF Size: 8.625 feet: 1425 WITH 675 SX CMT

\$203.13

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/11/2004 9:30 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PUMP 100# HULLS WITH 25 SX CMT. PLUG AT 1525-1325'. PLUG AT 720' WITH 40 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/11/2004 12:00 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

CIBP @ 5975' WITH 2 SX CMT. LOAD HOLE WITH MUD. 1ST PLUG AT 1525' WITH 70 SX CMT. 2ND PLUG PULL TO 725' & SPOT 50 SX CMT. PULL CASING OUT OF HOLE. FILL 8 5/8" WITH 25 SX CMT. STAYED FULL.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 6110 | 6130 |      |          |
| 6096 | 6110 |      |          |
| 6025 | 6030 |      |          |

RECEIVED  
FEB 19 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ORR ENTERPRISES. RECOVERED 2170' OF 2 7/8" CASING.

Plugged through: CSG

District: 01

RECEIVED  
FEB 12 2004  
KCC Dodge City

Signed [Signature] (TECHNICIAN)

INVOICED  
DATE 2-19-04  
INV. NO. 2004061197

Form SP 2/3