

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23246-00-00
Spot: N2NESESW Sec/Twnshp/Rge: 12-15S-13W
1250 feet from S Section Line, 2970 feet from E Section Line
Lease Name: KITCH Well #: 1
County: RUSSELL Total Vertical Depth: 3280 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: PO BOX 352 370 W WICHITA AVE
RUSSELL, KS 67665

SURF Size: 8.625 feet: 209

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/14/2004 12:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Order 135 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.
Arbuckle penetrated but very tight.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 02/14/2004 2:00 AM KCC Agent: HERB DEINES

Actual Plugging Report:

Perfs:

1st. Plug at 715' w/25 sxs.
2nd. Plug at 400' w/50 sxs.
3rd. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

RECEIVED
FEB 19 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed _____

(TECHNICIAN)

INVOICED
DATE 2-19-04
INV. NO. 2004061175

Form CP-2/3

FEB 17 2004