

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-21712-00-00
Spot: NWNE Sec/Twnshp/Rge: 19-17S-24W
660 feet from N Section Line, 1980 feet from E Section Line
Lease Name: SCHABEN C Well #: 1
County: NESS Total Vertical Depth: 4441 feet

Operator License No.: 9855
Op Name: GRAND MESA OPERATING COMPANY
Address: 200 E. 1ST STREET N. STE 307 FRMRS
WICHITA, KS 67202

PROD Size: 5.5 feet: 4440 WITH 300 SX CMT
SURF Size: 8.625 feet: 376 WITH 220 SX CMT

#144.33

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/03/2004 11:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: MIKE J FRITZLER Company: _____ Phone: (785) 798-3641

Proposed Plugging Method: SAND TO 4260' & 4 SX CMT. PRESSURE TEST CASING. RUN BOND LOG AND CIRCULATE CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/03/2004 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SAND TO 4260' & 4 SX CMT. PRESSURE TEST CASING TO 500#. HELD. RAN BOND LOG. FOUND NO CMT FROM 1800' TO SURFACE. FOUND PERMIAN AT 1050'. SHOT HOLES IN CASING AT 1050' & PUMPED 175 SX CMT. MAXIMUM PRESSURE 1500#. SHUT IN PRESSURE 1500#. TIED ONTO BACKSIDE & PUMPED 50 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN PRESSURE 500#.

Perfs:

Top	Bot	Thru	Comments
4368	4374		

RECEIVED
FEB 19 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED
FEB - 5 2004
KCC Dodge City

Signed *Michael Maier*
(TECHNICIAN)

INVOICED
DATE 2-19-04
INV. NO. 200406198