

6 010539

7-22 15-147-20207-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 11-19-75
C NE SE, SEC. 4, T 1 S, R 18 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5352

Operator: Baird Oil Co.
Name & Address: Box 428
Logan, Kansas

Lease Name Walker Well # 5

County Phillips 109.36

Well Total Depth 3365 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 219

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas

Company to plug at: Hour: _____ Day: 22 Month: July Year: 19 87

Plugging proposal received from Millard Kelso

(company name) Chase, Independence, Ks. (phone) _____

were: Order 200 sks cement 65/35 Pozmix 10% Gel, 2% Lite. 50# Flocele, 600# Hulls.

4 1/2 csg. at 3429. Shot at 1600' -1400' -1200'.

Recovered 1200' of 4 1/2 csg. Perf 3234 - 3354.

Elev. 1979. Sand bottom to 3180 and 4 sks cement on top.

Dakota 1150
829

Plugging Proposal Received by

D. F. B.
(TECHNICIAN)
Dale F. Balthazor

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: _____ Day: 22 Month: July Year: 19 87

ACTUAL PLUGGING REPORT

Pumped down 8 5/8 225 sks cement and 600# Hulls.

56# Flocele. Max pressure 1200. Closed w/1200# pressure.

(25 sks of cement followed by 200 sks of cement with 600# Hulls.) RECEIVED

AUG - 6 1987

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-6-87

INV. NO. 17722

Signed *Dale F. Balthazor*

(TECHNICIAN)

Dale F. Balthazor