

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-20449-00-00
Spot: CSESW Sec/Twnshp/Rge: 4-1S-18W
660 feet from S Section Line, 1980 feet from W Section Line
Lease/Unit Name: WALKER B Well Number: 1
County: PHILLIPS Total Vertical Depth: 3555 feet

Operator License No.: 32819
Op Name: BAIRD OIL COMPANY LLC
Address: 113 W. MAIN - PO BOX 428
LOGAN, KS 67646

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 221 175 sx cmt
Production: Size 4.5 feet: 3553 690 sx cmt
Liner: Size feet: 115.54

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/29/2001 9:00 AM

Plug Co. License No.: 32819 Plug Co. Name: BAIRD OIL COMPANY LLC

Proposal Rcvd. from: JIM R. BAIRD Company: BAIRD OIL COMPANY LLC Phone: (785) 689-7456

Proposed
Plugging
Method:

Ordered 9 yards Redi-Mix - 5 sxs common cement - 3000# sand with 42 gallons water per yard.

Plugging Proposal Received By: CARL GOODROW

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 08/29/2001 10:00 AM

KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 221' w/175 sxs cwc. 4 1/2" set at 3553'. 1st stage 240 sxs.
D.V. at 1745' w/450 sxs cwc.
Prod.Perfs 3395' - 3482'. PBTD 3503'.
Filled 4 1/2" with 9 yards Redi-Mix.
Plug complete.

RECEIVED
SEP 11 2001
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Carl Goodrow

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 9-11-01

INV. NO. 2002060450

SEP 05 2001

BAIRD OIL COMPANY
BOX 428

#1 "B" WALKER

4-1-18W
C SE SW

LOGAN, KS 67646

CONTR ABERCROMBIE DRILLING

CTY PHILLIPS

GEOLOG JERRY MCLEOD


FIELD HUFFSTUTTER

ELV 2112 KB SPD 8/1/84

CARD
ISSUED

11/22/84

IP P 14 BO & 74 BWPD
LKC 3395-3482 OA



LOG	Tops	Depth/Datum	API 15-147-20,449
TOP		3088-976	8 5/8 " 214.71, 4 1/2 " 3553
HEEB		3280-1168	DST (1) 3341-70 (LKC) / 45-45-45-45, REC 10' OIL SPKD M, 80' WM, 30' SW, SIP 667-648#, FP 59-59 / 78-78#
TOR		3310-1198	DST (2) 3367-90 (LKC) / 30-45-30-45, REC 10' OIL SPKD M, SIP 707-677#, FP 39-39 / 59-59#
LANS		3324-1212	DST (3) 3389-3412 (LKC) / 45-45-45-45, REC 40' CL GSY OIL, 50' MCO, SIP 599-570#, FP 49-49 / 59-59#
BKC		3526-1414	DST (4) 3464-85 (LKC) / 60-60-60-60, REC 159' CL GSY OIL, 7' MCO, SIP 305-285#, FP 49-78 / 98-98#
RTD<D		3555-1443	MICT - CO, PF (LKC) 3395-3482 OA, AC 1000G (28%) & 500G (15%), SWB DWN, SO, POP, P 14 BO & .74 BWPD

NOTE: CORRECTION 8/30/84 - ORIGINALLY FIRST REPORTED AS 70'E, C W/2 SE SW

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

3395-3482 OA