

4-041500

7-12

15-147-20184-00-00

API number: 15- - 1-75

to:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE NE /4 SEC. 09 , 01 S, 18 W
4950 feet from S section line
330 feet from E section line

Operator license# 31070 Lease J. Imm well # 2

Operator: Eagle River Energy Corporation County Phillips

Address: 7060 S. Yale Well total depth 3480 feet 113.10
Suite 609 Conductor Pipe: 0 inch @ 0 feet
Tulsa, Oklahoma 74136 Surface pipe 8 5/8 Inch @ 253 feet
w/200 sx.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 12 Month: July Year: 93

Plugging proposal received from: Jerry Rice

Company: Eagle River Energy Corporation Phone:

Were: 6" casing set @ 3483' w/250 sxs. cement. Perfs. @ 3265' -
3445'. Anhy. @ 1670' - Dakota @ 1180' - W.L.M. @ 3400' - T.O.F. @ 1300'.
Order 300 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 300# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 6:00P.M., Day: 12, Month: July, Year: 93

Actual plugging report: Squeezed in 4 sxs. gel followed with 50 sxs.
cement, and 15 sxs. gel, plus 135 sxs. cement - wait on water for 30 min.
Squeezed 50 additional sxs. cement. Max. 500#. S.I. 500#.
Hooked-up to 8 5/8" S.P. Squeezed 25 sxs. cement with 100# hulls.
Max. 500#. S.I. 400#.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did observe the plugging.

Dennis L. Hamel
CONSERVATION DIVISION
Wichita, Kansas

(agent)

Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION

SEP 13 1993

INVOICED

SEP 14 1993

DATE

INV. NO. 38628