

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- ADW 15-147-20250-00-00

CNW-NW, Sec. 13, T 1 S, R 18 W/E

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5069

Lease Name Grocke Well # 1

Operator: Argonaut Energy Corp.
Name & Address: P.O. Box 4060
Amarillo, Tx. 79106

County: Phillips

Well Total Depth 3660' feet

Conductor Pipe: Size _____ feet _____

Surface Casing: Size 8 5/8" feet 910' w/170.0x

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing License Number _____

Address Chase, Kansas

Company to plug at: Hour: 11:00AM Day: 9 Month: 12 Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO Bob Bruneman

(company name) Kelso Casing (phone) _____

were: 4 1/2" cog @ 3654' w/150.0x - P.B. 3638'

Reps @ 3401' to 3635' -> Plug back w/ 25.0x cement

& 25.0x cement w/ hull -> Pump wiper plug to 3000'

Rec. 1407' 4 1/2" cog. / Ordered 190.0x 50% poz. 62 gel,

30.0x gel, 5 hulls + 8 5/8" plug

Signed Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:00PM Day: 2 Month: 12 Year: 1982

ACTUAL PLUGGING REPORT Plugged in 3 hulls -> 3 gel -> 50.0x cement ->

7 gel -> 10.0x cement w/ hull -> 10 gel -> Rel. Plug -> 70.0x cement

w/ hull - Max PSI 300#

Shut-in PSI 150#

Remarks: _____

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1982

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed Dennis L. Hamel
(TECHNICIAN)

INVOICED
DATE 12-28-82
INV. NO. 2024-W