

6 050159

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 147-20,470 -00-00 *of*

NW SE SWSEC. 14, T 1 S, R 18 *W/E*

990 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8572

Lease Name Chestnut Well # 1

Operator: Reach Oil Corp.

County Phillips 117.65

Name & Address 3751 E. Douglas

Well Total Depth 3620 feet

Wichita, Ks. 67218

Conductor Pipe: Size 0 feet

Surface Casing: Size 8⁵/₈ feet 217 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor R & C Drilling License Number 9087

Address Box 296 Hays, Ks.

Company to plug at: Hour: PM Day: 4 Month: January Year: 19 85

Plugging proposal received from Don Weis

(company name) R&C Drilling (phone) _____

were: Order 195 lbs. 50/50 pozmix 6% gel 3% cal. cl. 1 sk flo-cel 1 sk hulls and 8⁵/₈" plug. Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part XX None _____

Operations Completed: Hour: 8 AM Day: 4 Month: January Year: 19 85

ACTUAL PLUGGING REPORT

1st plug @ 1790 w/25 sks

2nd plug @ 1220 w/110 sks 1 sk flo-cel

3rd plug @ 240 w/40 sks

4th plug @ 40 w/ 8⁵/₈" plug and 1 sk hulls and 10 sks cmt

10 sks in Rat Hole

Cemented by Sun

RECEIVED STATE CORPORATION COMMISSION

JAN 17 1985

Remarks: Checked by Dale Balthazor

CONSERVATION DIVISION
(If additional description is necessary, use BACK of this form.) Wichita, Kansas

INVOICED

(did not) observe this plugging.

DATE 1-28-85

Signed Gilbert P. Leikey 13 16-85 mds
(TECHNICIAN)

INV NO. 6664