

4-042000

12-17

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-147-20,082-0000

C SE SW /4 SEC. 10, 01 S, 18 W  
660 feet from S section line  
3300 feet from E section line

Operator license# 31569  
Operator: Bach Oil Production  
Address: R.R.1 - Box 28  
Phillipsburg, Kansas 67661

Lease: O'Neil Well # 1  
County: Phillips 113.43  
Well total depth 3490 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface Pipe: 8 5/8 Inch 210 Feet  
W/145 sxs.cmt.

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 17 Month: December Year 1998

Plugging proposal received from: Jason Bach - Leland Bach

Company: Bach Oil Production Phone: 785-476-5254

Were: 4 1/2" casing set at 3440' w/200 sxs cement.

Ordered 250 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.  
Anhy. at 1675' - Dakota at 1150'.

RECEIVED  
STATE CORPORATION COMMISSION  
01-5-1999  
JAN - 5 1999

CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[ ], Part[ X ], None[ ]

Completed: Hour: 3:00 P.M. , Day 17, Month: December , Year: 1998

Actual plugging report: R.I.H. with tubing to 1750'. Spotted 135 sxs cement with 400# hulls to circulated at surface. P.O.O.H. with tubing and squeezed casing with 65 sxs cement to Max. P.S.I. 500#. S.I.P. 200#. Hooked-up to 8 5/8" S.P. Squeezed 50 sxs cement with 100# hulls. Max. P.S.I. 250#. S.I.p. 100#.

Remarks:

Condition of casing(in hole): GOOD  BAD  Anhy.plug: YES  NO   
Bottom plug(in place): YES , CALC , NO  Dakota plug: YES , NO   
Plugged through TUBING  CASING  . Elevation: G.L.

I did[ X ] / did not[ ] observe the plugging.

*Dennis J. Hamel*  
(agent)

Form CP-2/3

JAN 06 1999

60514

12-17

AUG 27 1999