

State of Kansas



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

FEB 26 1969

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-147-20064-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Fickle of Red Tiger Drlg. has this date requested permission to plug the following described well:

Mr. Fickle guarantees payment of the plugging fee.

Operator's full Name: Don H. Peaker Et al

Complete Address: box 1595 Pueblo, Colo.

Lease Name: Francis Well No. 2

Location: NE NE NW Sec. 14 Twp. 1 Rge. (E)(W) 18

County: Phillips Total Depth 3580 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Fickle was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 1050' and displace

70 sk cmt thru drill pipe. Heavy mud to 180' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar. Plug rat hole with

2 sk cmt.

Very truly yours,

Geo. F. Wassen
Conservation Division Agent