



ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-147-20024-00-00

RECEIVED  
12-11-1967  
DEC 11 1967  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Ogle of Red Tiger Drlg. has this

date requested permission to plug the following described well:

Mr. Ogle guarantees payment of the plugging fee.

Operator's full Name: Don H. Peaker, Etal

Complete Address: Box 1595 Pueblo, Colorado

Lease Name: Blanche M. Francis Well No. 1

Location: C SW NW Sec. 14 Twp. 1 Rge. 18 (E)(W) X

County: Phillips Total Depth 3525 Oil Well

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Ogle was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 1050' and displace  
100 sc cement thru drill pipe. Heavy mud to 210' set cementing plug and  
displace 25 sc cement thru drihl pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole  
with 2 sc cement.

Very truly yours,

Geo F. Marshall  
Conservation Division Agent