

API NUMBER 15-065-D1577-00-00

LEASE NAME Diebolt

WELL NUMBER 2

990 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 35 TWP. 9S RGE. 23 (E) or (W)

COUNTY Graham

Date Well Completed 7-5-7-1-1951

Plugging Commenced 2-12-04

Plugging Completed 2-16-04

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Beren, Inc.

ADDRESS P.O. Box 723 Hays, KS 67601

PHONE (785) 628-6101 OPERATORS LICENSE NO. 5364

Character of Well oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)
 by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation L-KC Depth to Top _____ Bottom _____ T.D. 4126

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface csg.		212	8 5/8	212	0
	prod. csg.		3959	5 1/2	3959	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set:
Rig up Karst well ser. Run thg catcher got on plug 3500' no fill up. Release lockset. Pull thg lockset. Put swedge in csg. Run thg open ended thg @ 3690'. Hook to 8 5/8 Mix 50 SX 60/40 pos 10% gel no pressure. Hook to thg Mix 115 SX 60/40 pos 10% gel 300# hulls. Pull to 2180 Mix 140 SX 60/40 pos 10% gel 300# hulls circ to surface. Pull thg Hook to 5 1/2 Mix 20 SX 60/40 pos 10% gel Max press. 1000# shut in off Check 8 5/8 standing full.
 Jay Pfeifer KCC witness.

Name of Plugging Contractor Karst Well Ser. / Beren License No. 99998

Address Russell, KS Wichita

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc. Beren, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Bob Grant (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filled the the same are true and correct, so help me God.

(Signature) Bob Grant


(Address) P.O. Box 723 Hays, KS

SUBSCRIBED AND SWORN TO before me this 20th day of February, 2004

Marion Sue Vance
 Notary Public

My Commission Expires: 4-30-06

RECEIVED
 FEB 24 2004
 KCC WICHITA



KCC
 FEB 23 2004
 HAYS, KS