

RECEIVED

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION FEB 26 2004 OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

KCC WICHITA Type or Print on this Form Form must be Signed All blanks must be Filled

Form CP-4 December 2003

Lease Operator: EOG Resources, Inc.

Address: 20 North Broadway, Suite 800 Okla City, OK 73102

Phone: (405) 239-7800 Operator License #: 5278

Type of Well: gas Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 2/02/2004 (Date)

by: Steve Durrant (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Chester Depth to Top: 6110' Bottom: 6130' T.D. 6250'

Morrow "B" Depth to Top: 6025' Bottom: 6030' T.D. 6080'

Depth to Top: Bottom: T.D.

API Number: 15-119-21004-00-00

Lease Name: Classen 14

Well Number: # 1

Spot Location (QQQQ): S/2-SE-660

Feet from North / South Section Line

1320 Feet from East / West Section Line

Sec. 14 Twp. 34 S. R. 27 East West

County: Meade

Date Well Completed: 10/26/1999 11-18-1999

Plugging Commenced: 2/10/2004

Plugging Completed: 2/11/2004

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Includes handwritten entries for Surface, Prod surface, CIBP 5975, and CIBP 6080.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Existing CIBP @ 6080'. RU wireline trk & GIH w/ 2 7/8" CIBP @ 5975'; load csg w/ 30 bbl mud & set CIBP. Cap w/ 1/2 sk cement. Cut 2 7/8" csg @ 2170' & pull end of tbg up to 1525'. Mix & pump 100 sks class "C" cement up to 1165'. Pull tbg up to 720' & spot 40 sks class "C" cement up to 620'. POH w/ tbg & top out 40' to surface w/ 12 sks cement.

Name of Plugging Contractor: Orr Enterprises, Inc. License #: 33338

Address: P. O. Box 1706 Duncan, Okla 73534

Name of Party Responsible for Plugging Fees: EOG RESOURCES, INC.

State of Oklahoma County, Stephens, ss.

Ronald E. Orr (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature]

(Address) PO Box 1706 Duncan, OK 73534

SUBSCRIBED and SWORN TO before me this 12th day of February, 2004

[Handwritten Signature] My Commission Expires: 4-13-04 Notary Public