

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
FEB 26 2004
KCC WICHITA

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: EOG Resources , Inc.
Address: 20 North Broadway , Suite 800 Okla City , OK 73102
Phone: (405) 239 - 7800 Operator License #: 5278
Type of Well: gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 2/02/2004 (Date)
by: Steve Durrant (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Chester Depth to Top: 5953' Bottom: 6055' T.D. 6300'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-025-21183-00-00
Lease Name: Theis 6
Well Number: # 3
Spot Location (QQQQ): NW - SE - SE
990 Feet from North / South Section Line
990 Feet from East / West Section Line
Sec. 6 Twp. 35 S. R. 25 East West
County: Clark
Date Well Completed: 4/23/1999
Plugging Commenced: 2/05/2004
Plugging Completed: 2/09/2004

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	818'	8 5/8"	818'	none
		surface	6300'	4 1/2"	6300'	1760'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

POH w/ tbg ; RU wireline trk & GIH w/ 4 1/2" CIBP . Load csg w/ mud (90 bbl) . Set CIBP @ 5903' & cap w/ 2 sk cement .
Weld on pull sub . Cut & pull 1760' of 4 1/2" csg . Run tbg @ 918' . Mix & pump 100 sks class "C" cement
Est TOC @ 575' . WOC 3 hrs . Tag TOC @ 615' . POH & top out 40' to surface w/ 12 sks cement.

Name of Plugging Contractor: Orr Enterprises , Inc. License #: 33338
Address: P. O. Box 1706 Duncan , Okla 73534

Name of Party Responsible for Plugging Fees: _____
State of Oklahoma County, Stephens , ss.

Ronald E. Orr (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____

(Address) Po Box 1706 Duncan, OK 73534

SUBSCRIBED and SWORN TO before me this 12th day of February, 2004
Graet L Sullivan My Commission Expires: 4-13-04
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202 BW