

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED FEB 25 2004 KCC WICHITA Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Shakespeare Oil Company, Inc. Address: 202 West Main St. Phone: (618) 548-1585 Operator License #: 7311 Type of Well: Oil D&A Docket #: The plugging proposal was approved on: 2/8/04 by: Herb Dinas Deines Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (If needed attach another sheet) N/A Depth to Top: Bottom: T.D. 4688

API Number: 15-109-20720-00-00 Lease Name: Moore-Teeter Well Number: 1-10 Spot Location (QQQQ): E/2 - W/2 - W/2 - E/2 2654 60/40 Feet from North South Section Line 2190 Feet from East West Section Line Sec. 10 Twp. 13 S. R. 32 East West County: IOGAN Date Well Completed: 2/8/04 Plugging Commenced: 2/8/04 Plugging Completed: 2/8/04

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: Surf, 0, 235'/220, 8 5/8", 220' 223, 0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rotary mud from 4689' to 2520', 2395' to 1465', 1415' to 275', and 75' to 40'. Cement plugs from 2520' to 2395', 1465' to 1415', 275' to 75', 40' to 0', 15 sx mousehole & 10 sx rathole. A total of 200 sx 60/40 Pozmix, 6% gel & 1/4#/sx Floseal was placed by drillpipe and cemented by Allied Cementing Co., Inc.

Name of Plugging Contractor: Murfin Drilling Co. Rig #20 License #: 30606 Address: 250 N. Water, Suite 300 Wichita, Kansas 67202 Name of Party Responsible for Plugging Fees: Shakespeare Oil Company, Inc. State of Illinois County, Marion, ss.

Donald R. Williams, Vice President (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Donald R. Will (Address) 202 West Main St., Salem, IL 62881

SUBSCRIBED and SWORN TO before me this 23rd day of February, 20 04 Dale K. Helpingstine My Commission Expires: 7-31-04

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

