

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-20431-00-00

LEASE NAME Anderson 'B'

RECEIVED

TYPE OR PRINT

WELL NUMBER 1

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

660 Ft. from N Section Line

4620 Ft. from E Section Line

FEB 18 2004
KCC WICHITA

SEC. 33 TWP. 16 RGE. 27 (E) or (W)

LEASE OPERATOR Abercrombie Energy, LLC

COUNTY Lane

ADDRESS Rt. #1, Box 56 Great Bend, Ks. 67530

Date Well Completed 5-13
3-7-1980

PHONE# (620) 793-8186 OPERATORS LICENSE NO. 32457

Plugging Commenced 2-13-04

Character of Well Oil

Plugging Completed 2-13-04

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-10-03 (date)

by Kevin Strube - Dodge City, Ks. (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Lans. KC Depth to Top 3994 Bottom 4315 T.D. 4622

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Lans. KC / Prod	Oil-water	4220	23	4 1/2	4391	None
		4262	66			
<u>Surf</u>		<u>290</u>	<u>290</u>	<u>8.625</u>	<u>290</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Mix 150# hulls 25 sxs 65/35 Poz displace with 42 Bbl. Gel & 14 Bbl. H2O w/1000#PSI standing.
Release pressure. Perf 4 shots 1240'. Could not pump into. Reperf @ 1000'. Mix 190 sxs
65/45 Poz 6% Gel. Displace down 4 1/2 shut in with 700#. Mix 140 sxs 65/35 Poz 6% Gel.
Displace down 8 5/8 - 4 1/2 ann. Shut in with 150#.

Name of Plugging Contractor Abercrombie RTD, Inc. Allied Cement License No. 30684 99996

Address Rt. #1, Box 56, Great Bend, Ks. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Abercrombie Energy, LLC?

STATE OF Kansas COUNTY OF Barton, ss.

E. L. Abercrombie

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same NOTARY PUBLIC - State of Kansas correct, so help me God.



(Signature) E. L. Abercrombie

(Address) Rt. #1, Box 56, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 16th day of February, 2004

Susan M. Urban
Notary Public

My Commission Expires: 7-29-2004