

3 022542

15.001. 01799-00-0

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: STATE OF KANSAS Fee FundName & FEE FUND PLUGGING

Address _____

AB oil well ☒ Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICELic. # 6372Address: BOX 386, RR4, CHANUTE, KANSAS 66720Company to plug at: Hour: 8:00A.M. Day: _____ 9 Month: 2 2004Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 800' THAT MAYHAVE BEEN CEMENTED IN FROM BOTTOM TO TOP. THE 2" CASING WAS OBSTRUCTED.THE PLUGGING PROPOSAL WAS TO DRILL OUT THE 2" CASING, TO PERFORATE THECASING SEVERAL TIMES, AND TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLEFULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent:

All _____

Part _____

☒TECHNICIAN
None _____

Operations Completed: Hour:

10:00A.M. Day: _____

9 Month: _____

2

2004

Actual Plugging Report: _____

THE 2" CASING WAS DRILLED OUT TO 700'. THE 2" CASING WAS PERFORATED AT 500',AT 350', AND THE 2" CASING WAS PERFORATED AT 200'. 3/4" PIPE WAS RAN INTO THE2" CASING TO 700'. CEMENT WAS PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATEDFROM THE 2" CASING AT SURFACE. THE 3/4" PIPE WAS REMOVED. DISPLACEMENT WASFILLED FROM SURFACE.Remarks: (THE GPS DESIGNATION FOR THIS WELL IS NO.08.)(If additional description is necessary, use BACK of this form.)

I

DID

observe this plugging.

RECEIVED

FEB 17 2004

KCC WICHITA

API NUMBER CONTROL NO.20030097NE.SW,NW 1/4 Sec/Twp/Rge S.8-T.26S.-R.18E.3709 feet from south section line4487 feet from east section lineLease/Well# TUCKER 39County ALLENWell Total Depth 800' feetProduction Pipe: 2" Size Feet 800'Surface Casing: 8" Size Feet 20"

D & A _____

Signed:

Clayton P. Titel
TECHNICIAN