

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-20181-00-01
Spot: NWSWNW Sec/Twnshp/Rge: 26-15S-27W
3630 feet from S Section Line, 4950 feet from E Section Line
Lease Name: OWENS Well #: 1 SWD
County: GOVE Total Vertical Depth: 4342 feet

Operator License No.: 3122
Op Name: VINTAGE PETROLEUM, INC.
Address: 110 W. 7TH STREET
TULSA, OK 74119

PROD Size: 5.5 feet: 4334 w/100 sxs cmt
SURF Size: 8.625 feet: 347 w/225 sxs cmt
141 12

Well Type: SWD UIC Docket No: D21537.0 Date/Time to Plug: 02/17/2004 9:00 AM
Plug Co. License No.: 4072 Plug Co. Name: PLAINS INC
Proposal Rcvd. from: KEN SCHMIDT Company: VINTAGE PETROLEUM, INC. Phone: (405) 823-5290

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 10% gel - 22 sxs gel - 400# hulls.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/17/2004 1:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface pipe set at 347' w/225 sxs cement. 5 1/2" production casing set at 4334' w/100 sxs cement.
Stage collar set at 1924' w/375 sxs cement. Open hole from 4337' - 4427'.
Ran tubing to 4110' - pumped 40 sxs cement with 400# hulls.
Pulled tubing to 3800' - pumped 22 sxs gel.
Pulled tubing to 1900' - pumped 125 sxs cement. Cement to surface.
Pulled tubing to surface - pumped 18 sxs cement.
Max. P.S.I. 800#. S.I.P. 0#.
Connected to 8 5/8" surface casing - pumped 15 sxs cement.
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
4337	4427		

RECEIVED
FEB 24 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC.-TICKET #6521.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

HO.

INVOICED

DATE 2-25-04
TEL. NO. 2004061227

FEB 19 2004

THUNDERBIRD DRILLING, INC. #1 OWEN
 BOX 18407, WICHITA, KS.
 CONTR STRATA DRILLING CTY GOVE

26-15-27W
 NW SW NW

GEOL FROSTY COX FIELD WHITNEY WEST DISC.

E 2474 KB CM 6/4/73 CARD ISSUED 7/19/73 IP P 89 BOPD N/W
 MTSS 4334-4343

API 15-063-20,181

LOG TOPS	DEPTH	DATUM	
			8 5/8" 347/225SX; 5 1/2" 4334/100SX
ANHY	1919	+ 555	DST(1) 3800-3831/90", 1675' MW, BHP 1298-1289#/45", FP 69-796#
HEEB	3696	-1222	DST(2) 3881-3915/1 1/2", 30' M, BHP 1228-1176#/45", FP 52-61#
TOR	3717	-1243	DST(3) 3948-3978/1 1/2", 520' MW, BHP 796-787#/45", FP 61-277#
LKC	3736	-1262	DST(4) 3974-4015/1 1/2", 375' MW, BHP 1246-1211#/45", FP 61-208#
BKC	4036	-1562	DST(5) 4017-4180/1 1/2", 200' MW, BHP 1344-1306#/45", FP 121-182#
NRM	4090	-1616	DST(6) 4285-4320/1 1/2", 15' SOCM + TR FO, BHP 1125-1073#/45", FP 55-69#
PAWN	4169	-1695	DST(7) 4320-4332/1 1/2", 20' CO, 90' WM, W/SC OIL, BHP 1254-1228#/45", FP 43-69#
FT SC	4223	-1749	
CHER	4250	-1776	
MJSS	4314	-1840	
RLD	4342	-1868	
LTD	4343	-1869	

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

(OVER)

THUNDERBIRD DRILLING, INC. #1 OWEN

26-15-27W
 NW SW NW

DST(8) 4332-42/90" 12:15' CGO, 180' FRGY OIL, BHP 1176-1159//
 45", FP 61-519#

MICT, DRILL STAGE COLLAR SWB 9BOPH/2HRS SD/12HRS FU 2800' OIL
 SWB 8.33BOPH N/W/4HRS SD/12HRS FU 3500' OIL, POP