

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-03706-00-00
Spot: N2S2SE Sec/Twnshp/Rge: 25-11S-18W
660 feet from S Section Line, 1320 feet from E Section Line
Lease Name: MARSHALL Well #: 4
County: ELLIS Total Vertical Depth: 4065 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

L1 Size: 4.5 feet: 2079 w/275 sxs cmt
PROD Size: 5.5 feet: 3848 w/200 sxs cmt
SURF Size: 8.625 feet: 163 w/100 sxs cmt

#132"

Well Type: SWD UIC Docket No: D04346.0 Date/Time to Plug: 02/20/2004 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: STAN Company: MURFIN DRILLING CO., INC. Phone: (785) 483-1197

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 700# hulls.
Was packerless completion SWD.
Pulled 150 joints 2 3/8" fiberglass tubing - average joint 20.25' - tally of 3037'.
Fluid level 600'.
Squeezed 10-31-1955 - 658' w/375 sxs and 805' w/250 sxs.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/20/2004 12:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran steel 2 3/8" tubing to 2100'.
Allied pumped 200 sxs 60/40 pozmix - 10% gel with 400# hulls - circulated cement.
P.T.O.H. Allied squeezed with 100 sxs cement and 300# hulls.
Max. P.S.I. 600#. S.I.P. 300#.

RECEIVED
FEB 25 2004
KCC WICHITA

Perfs:

Top	Bot	Thru	Comments
3846	4065		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED
2-25-04
2004061220

FEB 24 2004

WALTERS DRILLING

#4

MARSHALL

25-11-18W
N2 S2 SE

Contr.

ELLIS

County

E 1970 RB Comm. 1-1-55

Comp. 1-21-55

IP S W D W

Tops	Depth	Datum
ANH	1200	770
TOP	2952	980
HEEB	3190	1220
LANS	3237	1267
SH GONG	3511	1511
CH GONG	3608	1638
REW SIMP	3651	1681
ARB	3773	1803
TD	4065	2095

Casing
8" 163

BEMIS-SHUTTS POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

IMAGED