

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20669-00-00
Spot: E2SWNW Sec/Twnshp/Rge: 23-16S-42W
2160 feet from N Section Line, 1030 feet from W Section Line
Lease Name: HOFFMAN Well #: 1
County: GREELEY Total Vertical Depth: 5308 feet

Operator License No.: 3581
Op Name: RED OAK ENERGY, INC.
Address: P.O. BOX 783140 7701 E. KELLOGG ST
WICHITA, KS 67207

PROD Size: 5.5 feet: 5299 WITH 175 SX CMT
SURF Size: 8.625 feet: 625

172⁵¹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/19/2004 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: KEVIN DAVIS Company: RED OAK ENERGY Phone: (316) 652-7373

Proposed Plugging Method: PUMP 25 SX CMT & 100# HULLS. PLUG AT 1850' WITH 80 SX CMT. PLUG AT 925' WITH 72 SX CMT. TOP OFF WITH 13 SX CMT. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/19/2004 1:15 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 5172'. PERFORATED AT 1850' SQUEEZED WITH 220 SX CMT. CIRCULATED TO SURFACE BETWEEN 8 5/8" X 5 1/2". 1ST PLUG RUN TUBING IN HOLE TO 4990'. PUMPED 25 SX CMT WITH 100# HULLS MIXED IN. 2ND PLUG PULL TUBING OUT OF HOLE TO 1850'. PUMPED 80 SX CMT DISPLACED WITH 3 BBL WATER. 3RD PLUG PULL TUBING OUT OF HOLE TO 925'. CIRCULATED CMT TO PIT WITH 72 SX CMT. 4TH PLUG PULL TUBING OUT OF HOLE & TOPPED OFF WITH 13 SX CMT. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS 25 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN PRESSURE 500#.

Perfs:

Top	Bot	Thru	Comments
4992	4996		

RECEIVED
FEB 26 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01

RECEIVED
FEB 24 2004
KCC Dodge City

Signed

Kevin D. Strube

(TECHNICIAN)

INVOICED
DATE 2-26-04
INV. NO. 2004061234

Form CP 23