

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-071-20254-00-00  
Spot: NENENESW Sec/Twnshp/Rge: 32-17S-40W  
2419 feet from S Section Line, 2911 feet from E Section Line  
Lease Name: SMITH CATTLE INC Well #: 10  
County: GREELEY Total Vertical Depth: 3030 feet

Operator License No.: 6085  
Op Name: SMITH RANCH COMPANY  
Address: HC 2 BOX 201  
SHARON SPRINGS, KS 67758

CIBP Size: feet: 2933 WITH 2 SX CMT  
PROD Size: 4.5 feet: 3030 WITH 300 SX CMT  
SURF Size: 8.625 feet: 312 WITH 225 SX CMT

#98 48

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/23/2004 12:30 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DAVE OLSON Company: SMITH RANCH COMPANY Phone: (785) 852-4653

Proposed Plugging Method: CIBP @ 2933' WITH 2 SX CMT. BOND LOG. PERFORATE & PUMP CMT DOWN 4 1/2" CASING. PRESSURE TEST. CHECK BACKSIDE.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/23/2004 3:45 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 3030'. CIBP @ 2933' WITH 2 SX CMT SPOTTED ON TOP BY DUMP BAILER. LOADED HOLE WITH FRESH WATER. PRESSURED UP TO 500#. RAN BOND LOG AND FOUND CMT FROM 0'-640'. PERFORATED AT 1575'. PUMPED DOWN 4 1/2" CASING 170 SX CMT. MAXIMUM PRESSURE 700#. SHUT IN PRESSURE 300#. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 0 SX CMT. MAXIMUM PRESSURE 700#. SHUT IN PRESSURE 700#.

Perfs:


Top	Bot	Thru	Comments
2983	2988		

RECEIVED  
FEB 26 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Kevin D. Strube

(TECHNICIAN)

INVOICED  
DATE 2-26-04  
INV. NO. 2004061235

Form 1078