

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-071-20189-00-00  
Spot: SWNEENE Sec/Twnshp/Rge: 5-18S-40W  
3963 feet from S Section Line, 797 feet from E Section Line  
Lease Name: SMITH CATTLE INC Well #: 1  
County: GREELEY Total Vertical Depth: 3044 feet

Operator License No.: 6085  
Op Name: SMITH RANCH COMPANY  
Address: HC 2 BOX 201  
SHARON SPRINGS, KS 67758

PROD Size: 4.5 feet: 3044 WITH 475 SX CMT  
SURF Size: 8.625 feet: 258 WITH 200 SX CMT

#98<sup>93</sup>

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/23/2004 8:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DAVE OLSON Company: SMITH RANCH COMPANY Phone: (785) 852-4653

Proposed Plugging Method: CIBP @ 2665' WITH 2 SX CMT. RUN BOND LOG. PERFORATE AT 1553', PUMP 90 SX CMT TO SURFACE. PRESSURE TEST. CHECK BACKSIDE.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/23/2004 12:30 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 3044'. SET CIBP @ 2665. COULD NOT GET ANY LOWER. SPOTTED 2 SX CMT ON TOP BY DUMP BAILER. LOADED HOLE WITH FRESH WATER. PRESSURED UP TO 500#. RAN BOND LOG TO FIND TOC. CMT @ 66'. GOOD CMT @ 160'. PERFORATED AT 1553'. PUMPED 90 SX CMT. MAXIMUM PRESSURE 1200#. SHUT IN PRESSURE 700#. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 15 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN PRESSURE 500#.

Perfs:


Top	Bot	Thru	Comments
2963	2973		

RECEIVED  
FEB 26 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed \_\_\_\_\_

*Kevin D Strub*

(TECHNICIAN)

INVOICED

DATE 2-26-04

INV. NO. 2004061235

Form SP-103