

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-00624-00-00
Spot: NENWSE Sec/Twnshp/Rge: 22-18S-26W
2970 feet from N Section Line, 1650 feet from E Section Line
Lease Name: EDWARDS Well #: 1
County: NESS Total Vertical Depth: 4450 feet

Operator License No.: 31627
Op Name: WHITETAIL CRUDE, INC
Address: N HWY 283 PO BOX 544
NESS CITY, KS 67560

PROD Size: 5.5 feet: 4449 WITH 70 SX CMT
SURF Size: 8.625 feet: 302 WITH 175 SX CMT

63
1144

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/13/2004 10:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: MIKE J FRITZLER Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: PUMP 100# HULLS & 30 SX CMT. PLUG AT 1300' WITH 30 SX CMT. PERFORATE @ 1100' & PUMP 80 SX CMT. PLUG AT 320' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/13/2004 3:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

Perfs:


ANHYDRITE @ 1900'. OUT OF HOLE @ 2400'. 1ST PLUG AT 2350' WITH 100# HULLS & 30 SX CMT. 2ND PLUG AT 1300' WITH 30 SX CMT. WAIT ON CMT 1 1/2 HOURS. TEST 5 1/2" CASING TO 300 PSI. 3RD PLUG PERFORATE 5 1/2" @ 1100'. PUMPED 80 SX CMT OUT PERFS AND LEFT 500' CMT IN CASING. 4TH PLUG AT 320' WITH 50 SX CMT. 5TH PLUG AT 40-0' WITH 10 SX CMT.

RECEIVED
FEB 26 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. RECOVERED 438' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Steve Durrant

(TECHNICIAN)

INVOICED

DATE 2-26-04

INV. NO. 2004061237