

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-21794-00-01
Spot: S2NWNWNE Sec/Twnshp/Rge: 35-22S-12W
4820 feet from S Section Line, 2310 feet from E Section Line
Lease Name: MCCUNE Well #: A1
County: STAFFORD Total Vertical Depth: 3750 feet

Operator License No.: 32610
Op Name: G T PETROLEUM, INC.
Address: RR 2, BOX 32
STAFFORD, KS 67578

CIBP Size: feet: 3510
PROD Size: 5.5 feet: 3749 WITH 125 SX CMT
SURF Size: 8.625 feet: 225

#121⁸⁸

Well Type: EOR UIC Docket No: E24628.1 Date/Time to Plug: 02/20/2004 10:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: BENNIE GRIFFIN Company: Phone:

Proposed Plugging Method: SAND BOTTOM TO 3350' & 5 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 260' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/20/2004 3:30 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

PBTD 3510'. SANDED TO 2800' & 5 SX CMT. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 260' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3640	3644		
3405	3466		

RECEIVED
FEB 26 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID. RECOVERED 1500' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
FEB 23 2004
KCC Dodge City

Signed _____

[Signature]

(TECHNICIAN)

INVOICED

2.26.04

2004061228

Form CP-233