

API NUMBER 15-163-20257-00-00

LEASE NAME Nutsch

WELL NUMBER 6

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Com. Div.  
office within 30 days.

2310 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 3 TWP. 10S RGE. 20 (E) or (W)

COUNTY Rooks

Date Well Completed 12-11-69

Plugging Commenced 2-12-04

Plugging Completed 2-12-04

LEASE OPERATOR Berexco, Inc.

ADDRESS P.O. Box 723 Hays, KS 67601

PHONE (785) 628-6101 OPERATORS LICENSE NO. 5363

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)  
by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Arb. Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3802

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface csg.		219	8 3/8	219	0
	Prod. csg		3798	5 1/2	3798	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
Rig up Karst well ser. Poorboy 8 5/8 to 5 1/2. Run open ended tbg to 3211 Pull 1jt to 3182 Mix 120 SX 60/40 PPS 10% gel 200# hulls. Pull tbg to 1585 Mix 130 SX 60/40 PPS 10% gel 400# hulls Circ to surf. Pull tbg. Hook to 5 1/2. Mix 20 SX 60/40 PPS 10% gel Max press 400# Shut in 400# Hook to 8 5/8 inst. Press Rick Williams KCC witness.

Name of Plugging Contractor Karst Well Ser/Berexco Inc License No. 99998

Address Russett, KS Wich. KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Rooks, ss.

Bob Grant (Employee of Operator) or (Operator) o above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Robert Grant



(Address) P.O. Box 723 Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 20<sup>th</sup> day of February 2004

Marion Sue Vance  
Notary Public

RECEIVED Commission Expires: 4-30-06

FEB 24 2004  
KCC WICHITA



Burr