

**KANSAS**  
**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

**RECEIVED**  
STATE CORPORATION COMMISSION  
JUL 27 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Earl Brubaker 15-147-20081-00-00  
Complete Address Box 550 Rocky Ford, Colorado 81067  
Lease Name Stone Well No. 1  
Location N/2 SW NW Sec. 12 Twp. 1 Rge. (E) (W) 18  
County Phillips Total Depth 3560'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Southwest Casing Pulling, Co.  
Address Box 364 Great Bend, Kansas License No. 399  
Operation Completed: Hour 1:30 P Day 23 Month 7 Year 1970

The above well was plugged as follows:

Total Depth 3560' 8 5/8 csg set at 215' cwc 160 sk.  
4 1/2 csg set at 3559' cw 150 sk cmt.  
4 1/2 csg PBTB 3382' Perf. (3362-3364)  
Filled 4 1/2 csg W/sd (3350-3382) Dumped 4 sk cmt W/dump bailer. (3300-3350)  
Cutoff and recovered 1820' of 4 1/2 csg.  
Pumped 15 gel W/5 sk hulls -70 sk reg poz 6% -15 gel -plug and 55 sk reg poz 6%.  
Cmt. (0-230) Gel (230-740) Cmt (740-940) Gel (940-TD)

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Prof. Massey  
Well Plugging Supervisor

DATE 7/28/70  
INV. NO. 2295-W